

15-169-19060-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Saline County, Sec. 29 Twp. 15 Rge. 3 (E) #W

Location as "NE/CNW/SW" or footage from lines. C E/2 SE SW

Lease Owner: Walter Nelson

Lease Name: Johnson Well No. I

Office Address: 2072 Marc Salina, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) oil

Date well completed 19

Application for plugging filed May 1965

Application for plugging approved May 1965


Plugging commenced May 31 1965

Plugging completed 6-3 1965

Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Gilbert Toman

Producing formation Depth to top Bottom Total Depth of Well 3397' Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				4 1/2"		2,980'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plugged off bottom of hole with roc. Rock from 3397' to 3380'. Dumped 3 sx of cement. Mudded hole to 310'. Made 10' of rock bridge. Dumped 25 sx of cement. Mudded hole to 35'. Made 5' of rock bridge. Dumped 10 sx of cement, filling to the bottom of the cellar.

RECEIVED
STATE CORPORATION COMMISSION
JUN 14 1965
06-14-1965
CONSERVATION DIVISION
WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Art Lamb Casing Pulling Co.

Address 2809 King Hutchinson, Kansas

STATE OF Kansas, COUNTY OF Reno, ss.

Art Lamb (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Art Lamb

2809 King Hutchinson, Kansas

(Address)

SUBSCRIBED AND SWORN to before me this 2nd day of June, 1965

My commission expires January 5, 1966

Rudy Lamb
Notary Public.

et al
 Walter J. Nelson / Lease Owner
 Donald T. Ingling, Contractor

Section 29-15-3W
 Location: C R/2 SE SW
 County: Saline
 Production:
 Elevation: 1291 RB

Commenced: 12-19-61
 Completed: 1-10-62

Total Depth: 3397 (rotary)

Casing: 8 5/8" 334' (150 sacks cement)
 4 1/2" 3394 1/2' (75 sacks cement)

Figures below indicate bottom formation

80	surface clay	3100	Mississippi
215	shale	3112	Mississippi
220	lime	3130	shale
330	lime	3175	shale
335	lime	3197	shale
415	lime	3308	shale
595	lime and shale streaks	3325	shale
825	lime and shale	3380	shale
950	lime and shale	3393 1/2	shale
1220	shale and shells	3397	Maquoketa dolomite
1520	shale and shells	3397	Total Depth
1730	shale and shells		
1740	lime		
1865	lime		
1945	lime		
2035	lime		
2165	lime		
2265	lime		
2330	lime		
2450	lime		
2525	lime		
2615	lime		
2720	lime		
2850	shale		
2920	shale and lime		
3030	Mississippi		

05-20-1965

I certify this is a true and correct copy of the above mentioned well.

D. T. Ingling

STATE OF KANSAS, COUNTY OF SEDGWICK: ss.

Subscribed and sworn to before me, a Notary Public, in said county and state.

M. E. Beach
 Notary Public

My commission expires: Feb. 27, 1965.