


Give All Information Completely  
Mark Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Saline County, Sec. 26 Twp. 15 Rge. 3 (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines C NE NE  
Lease Owner Morrison Producing Company  
Lease Name Miller Well No. 1  
Office Address Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) \_\_\_\_\_  
Date well completed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging filed \_\_\_\_\_ 19\_\_\_\_  
Application for plugging approved \_\_\_\_\_ 19\_\_\_\_  
Plugging commenced 10-3-62 \_\_\_\_\_ 19\_\_\_\_  
Plugging completed 10-5-62 \_\_\_\_\_ 19\_\_\_\_  
Reason for abandonment of well or producing formation Depleted.



If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Gilbert Toman  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3275 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS				CASING RECORD		
FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	243'	None
				5-1/2"	3266'	2586'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Checked hole to 3275', sanded to 3250' and dumped 5 sacks of cement @ 3250' with dump bailer. ~~Bailed~~ Pulled 5" casing. Bailed fluid to 215', set 10' rock bridge and filled 8-5/8" casing to base of cellar with ready-mix cement.

PLUGGING COMPLETE.

STATE CORPORATION COMMISSION  
OCT 1 1962  
CONSERVATION DIVISION  
Wichita, Kansas  
10-12-1962

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor KNIGHT CASING PULLING COMPANY  
Address CHASE, KANSAS

STATE OF KANSAS COUNTY OF RICE, ss.  
Noel J. Knight (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Noel J. Knight  
Chase, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 10th day of October, 1962

My commission expires May 20, 1964  
Milton J. Volin Notary Public.

15-169-00476-00-00

MORRISON PRODUCING COMPANY

F. MILLER - WELL #1

Total Depth - 3280' C NB/4 NB/4  
 Contractor - Graves Drlg. Co. Section 26-15S-3W  
 Commenced - 9-25-61 Saline County, Kansas  
 Completed - 10-2-61 8 5/8" to 244'

<u>FORMATION</u>	<u>DEPTH</u>
Shale & lime shells	244
Shale	610
Lime	682
Shale	1234
Lime	1326
Shale & shells	1620
Shale	1884
Lime	1985
Shale & shells	2156
Lime	2521
Shale	2827
Lime	2990
Shale	3174
Lime	3199
Shale	3272
Lime	3280 T. D.

**RECEIVED**  
 STATE CORPORATION COMMISSION  
 SEP 26 1962  
 CONSERVATION DIVISION  
 09-26-1962

I hereby certify the foregoing statements to be true  
 and correct to the best of my knowledge.

GRAVES DRILLING COMPANY, INC.

STATE OF KANSAS )  
 ) SS  
 COUNTY OF BUTLER)

By John Graves

Subscribed and sworn to before me, a Notary Public, this  
3rd day of October, 1961.

Marlene Fairchild  
 (Notary Public)

My commission expires:  
November 23, 1963