

1 090364

11-27

API NUMBER 15- 171-20,460-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SE NW NE, SEC. 10, T. 19 S, R. 34 W XX

4290 feet from S section line

1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123

Lease Name Buehler "A" Well # 1

Operator: Pickrell Drilling Company, Inc.

County Scott

Name & Address 110 N. Market, Ste. 205

Well Total Depth 4925 <sup>160.06</sup> feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 328

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A  X

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pickrell Drilling Company, Inc. License Number 5123

Address 110 N. Market, Ste. 205, Wichita, KS 67202

Company to plug at: Hour: 1 a.m. Day: 27 Month: 11 Year: 1993

Plugging proposal received from Doyle Folkerts

(company name) Pickrell (phone) 316-262-8427

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 2375'

1st plug at 2380' with 50 sx cement, 2nd plug at 1000' with 80 sx cement,

3rd plug at 550' with 40 sx cement, 4th plug at 360' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Plugging Proposal Received by Steve Middleton (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None  X

Operations Completed: Hour: 3:30 a.m. Day: 27 Month: 11 Year: 1993

ACTUAL PLUGGING REPORT 1st plug at 2380' with 50 sx cement,

2nd plug at 1000' with 80 sx cement,

3rd plug at 550' with 40 sx cement,

4th plug at 360' with 50 sx cement,

5th plug at 40' with 10 sx cement,

6th plug to circulate rathole with 15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel 1/2# floseal by Allied.

(If additional description is necessary, use BACK of this STATE CORPORATION COMMISSION RECEIVED

INVOICED (XXX) did not observe this plugging.

Signed [Signature] (TECHNICIAN) DEC 01 1993

DATE 12-8-93

WV. NO. 39422

11-27

CONSERVATION DIVISION - 2  
Wichita, Kansas 67202

FOR KCC USE:

EFFECTIVE DATE: 11-8-93

DISTRICT # 17  
SEAT Yes No

State of Kansas  
NOTICE OF INTENTION TO DRILL

15 171-20,460-00-00

FORM C-1 7/91  
FORM MUST BE TYPED  
FORM MUST BE SIGNED  
ALL BLANKS MUST BE FILLED

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 11 - 8 - 93  
month day year

SE NW NE Sec 10 Twp 19 S. Rg 34 East  
West

OPERATOR: License # 5123  
Name: Pickrell Drilling Company, Inc.  
Address: 110 N. Market, Suite 205  
City/State/Zip: Wichita, Kansas 67202  
Contact Person: Don Beauchamp  
Phone: 316-262-8427

4290 feet from South line of Section  
1650 feet from East line of Section  
IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side)  
County: Scott  
Lease Name: Buehler "A" Well #: I  
Field Name: Wildcat

CONTRACTOR: License #: 5123  
Name: Company Tools

Is this a Pretested/Spaced Field? yes X no  
Target Formation(s): Mississippian  
Nearest lease or unit boundary: 900'

Well Drilled For: Well Class: Type Equipment:  
X Oil ... Enh Rec ... Infield X Mud Rotary  
X Gas ... Storage ... Pool Ext. ... Air Rotary  
... OWD ... Disposal X Wildcat ... Cable  
... Seismic: ... # of Holes ... Other  
... Other

Ground Surface Elevation: 3095± feet MSL  
Water well within one-quarter mile: yes X no  
Public water supply well within one mile: yes X no  
Depth to bottom of fresh water: 900'  
Depth to bottom of usable water: 1150' 995'

If OWD: old well information as follows:  
Operator:  
Well Name:  
Comp. Date: Old Total Depth

Surface Pipe by Alternate: 1 X 2  
Length of Surface Pipe Planned to be set: 300'  
Length of Conductor pipe required: None  
Projected Total Depth: 4900'  
Formation at Total Depth: Mississippian  
Water Source for Drilling Operations: well X farm pond other

Directional, Deviated or Horizontal wellbore? yes X no  
If yes, true vertical depth:

DMR Permit #:  
Will Cores Be Taken? yes X no  
If yes, proposed zone:

Exp. 5/3/94

AFFIDAVIT

300' Alt. II Reg. RECEIVED  
KANSAS CORPORATION COMMISSION

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Pusher Dale Falbert  
SPUD DATE 11-11-93 INIT. SD  
LENGTH SURFACE PLANNED 328-

RESERVE PIT STATUS- REMOVE FLUID LINED  
after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE  
SURFACE PIPE 8 1/2" @ 328 CONDUCTOR  
ANHYDRITE T- B- 238 ELEVATION

TD 4925 FORMATION

RAN PIPE @ DV TOOL ALT II DONE  
SX Y N

Arbuckle Plug @ Ft. W/ SX

Hug./Council @ Ft. W/ SX

Anhydrite Base @ 2380 Ft. W/ 50 SX

1/2 Base Anyh. @ 1000 Ft. W/ 80 SX

1/2, 1/2 Plug @ 550 Ft. W/ 40 SX

Bottom Surface @ 360 Ft. W/ 50 SX

40' Plug @ 40 Ft. W/ 10 SX

RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ SX

WATER WELL SX (Irr. Well Pond  
Hauling

TECHNICIAN SM DATE 11-24-93

TYPE OF CEMENT 60/40 670 1/4 Fibers

STARTING TIME : : (AM/PM) DATE 11-27-93

COMPLETION TIME 3 : 30 (AM/PM) DATE 11-27-93

CEMENT COMPANY Allied

RECEIVED  
STATE OF KANSAS  
CONSERVATION DIVISION  
Wichita, Kansas  
1993