

1080323

TO: STATE CORPORATION COMMISSION

API NUMBER 15-171-20,081-00-00
C NW NW SEC. 32, T 19, S, R 34 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME NOVAK WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY SCOTT 161.30

OPERATOR LICENSE # 30481 7/28

WELL TOTAL DEPTH 4963 FEET

OPERATOR: APOLLO ENERGIES, INC. PRODUCTION CSG: SIZE 4 1/2" @ 4962' WITH 175 SX

NAME AND ADDRESS 734-B N FOUR WHEEL DR SURFACE CASING: SIZE 8 5/8" @ 400' WITH 300 SX

ADDRESS KINGMAN, KS 67068

RECEIVED STATE CORPORATION COMMISS

ABANDONED OIL WELL X GAS WELL INPUT WELL INJ WELL D/A

AUG 1 2000

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529 CONSERVATION DIVISION Wichita, Kansas

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 9:30 AM DAY: 28 MONTH: 07 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM MONTE ANDREWS

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: CIBP @ 4850 & 4570. PERFS AT 4530-37

SANDED BACK TO 4340' WITH 4 SX CEMENT ON TOP. SPOTTED WITH BAILER. SHOT CASING AT 1800' COULDN'T PULL. SHOT CASING AT 1300' COULDN'T PULL. PUMP 40 SX CEMENT & THEN 40 SX CEMENT WITH 300# HULLS MIXED IN & DISPLACED WITH 2 SX GEL & 14 1/2 BBL WATER. SHOT CASING AT 810' PUMPED 4 SX GEL, 50 SX CEMENT WITH 200# HULLS & 4 SX GEL. PULLED CASING UP TO 430' PUMPED 50 SX CEMENT WELL CIRCULATING. PULLED CASING UP TO 40' PUMPED 10 SX CEMENT. HOLE STAYED LOADED.

PLUGGING PROPOSAL RECEIVED BY KEVIN STRUBE

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 12:00 AM DAY: 28 MONTH: 07 YEAR: 2000

ACTUAL PLUGGING REPORT SANDED BACK TO 4340' WITH 4 SX CEMENT ON TOP SPOTTED WITH BAILER. SHOT CASING @ 1800' COULDN'T PULL, SHOT CASING AT 1300', COULDN'T PULL. PUMPED 40 SX CEMENT & THEN 40 SX CEMENT WITH 300# HULLS MIXED IN & DISPLACED WITH 2 SX GEL & 14 1/2 BBL WATER. SHOT CASING @ 810'. PUMP 4 SX GEL, 50 SX CEMENT WITH 200# HULLS & 4 SX GEL. PULLED CASING UP TO 430' PUMPED 50 SX CEMENT WELL CIRCULATING. PULLED CASING UP TO 40' PUMPED 10 SX CEMENT HOLE STAYED LOADED.

REMARKS: USED 60/40 POZMIX 6% GEL 1 1/2" FLO SEAL BY ALLIED. RECOVERED 810' OF 4 1/2" CASING. (IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

DATE 8/31/00 SIGNED Kevin D. Strube (TECHNICIAN) FORM CP-2/3