

To: 1 8-15
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 171-20,464 -00-00

TECHNICIAN'S PLUGGING REPORT

Operator License # 30782
Operator: J W Oil Co./Jim Farr
Name & Address 209 Antelope.
Scott City, KS 67871

N/2 NW NE, SEC. 22, T 19 S, R 34 W/E
4850 feet from S section line
2310 feet from E section line
Lease Name Farr Well # 2
County Scott 160.71
Well Total Depth 4945 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 206

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Post & Mastin Well Service License Number 8438
Address 3210 W. Jones Av., Garden City, KS 67846

Company to plug at: Hour: 11 a.m. Day: 15 Month: 8 Year: 19 95
Plugging proposal received from Marvin Farr
(company name) J W Oil Co. (phone) 316-872-3951

were: 5 1/2" at 4943' w/200 sx cement, Perfs at 4776-81, 4033-4301, 4805-4809, 4854-60'
1st plug pump 50 sx cement and 200 lbs. hulls to 3800',
2nd plug pump 80 sx cement at 1250',
3rd plug pump 5 sx gel and 40 sx cement at 600',
4th plug pump 40 sx cement at 230', 5th plug pump 10 sx cement at 40'

RECEIVED
STATE CORPORATION COMMISSION
AUG 17 1995

Plugging Proposal Received by Richard Macey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 5 p.m. Day: 15 Month: 8 Year: 1995

ACTUAL PLUGGING REPORT 1st plug pumped 50 sx cement and 200 lbs. hulls to 3800'.
Shut in at 500#.
2nd plug pumped 80 sx cement at 1250';
3rd plug pumped 5 sx gel and 40 sx cement at 600',
4th plug pumped 40 sx cement at 230',
5th plug at 40', circulated cement.

Remarks: Used 60/40 Pozmix 6% gel 1/4# floseal by Allied. Recovered 1250' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICE
DATE 8-28-95
43373
8-15

Signed Richard M. Macey
(TECHNICIAN)