

To: 1 051454
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

7-18 1562
API NUMBER 15-171-20,420-00-00
C SW, SEC. 15, T 19 S, R 34 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 4981

1320 feet from S section line

3960 feet from E section line

Operator: Cholla Resources Inc.
Name & Address 1641 California St., Ste. 300
Denver, CO 80202

Lease Name Robinson Farms Well # 1-15

County Scott 160.87

Well Total Depth 4950 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 252

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Plains Inc. License Number 4072

Address P.O. Box 346, Ness City, KS

Company to plug at: Hour: 10 a.m. Day: 18 Month: 7 Year: 1991

Plugging proposal received from Max Parsons

(company name) Plains Inc. (phone) 913-798-3995

were: 5 1/2" at 4947' w/175 sx cement, PBTD 4947', Perfs at 4781-84, 4487-90'

1st plug set CIBP at 4400' with 2 sx cement on top,

2nd plug rip 5 1/2" casing at 1400' and 1450', pump down 5 1/2" with 200 sx cement and 100 lbs.

hulls.

3rd plug pump down 8 5/8" X 5 1/2" annulus with 70 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:35 a.m. Day: 18 Month: 7 Year: 1991

ACTUAL PLUGGING REPORT 1st plug set CIBP at 4400' with 2 sx cement on top,

2nd plug ripped 5 1/2" casing at 1400' and 1450', pumped down 5 1/2" with 200 sx cement and 100 lbs. hulls. Maximum pressure 900 psi and shut in 400 psi.

3rd plug pumped down 8 5/8" X 5 1/2" annulus with 70 sx cement. Maximum pressure 800 psi and shut in 500 psi.

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery. JUL 22 1991

(If additional description is necessary, use BACK of this form.)
observe this plugging.

DATE 8-8-91

INV. NO. 32589

Signed Richard M. Lacey
(TECHNICIAN)