

1-080189  
TO:

RECEIVED  
KANSAS DEPT OF REVENUE  
04-20-98

4-15  
API NUMBER 15-171-20,429-00-00

STATE CORPORATION COMMISSION SE-SW-SW SEC 15, T 19 S, R 34 W  
CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE  
WICHITA STATE OFFICE BLDG., 130 S. MARKET 2970 FEET FROM EAST SECTION LINE  
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT COUNTY SCOTT  
OPERATOR LICENSE # 71791 WELL TOTAL DEPTH 4913 <sup>159.67</sup> FEET  
OPERATOR: KYKON OIL & GAS, INC. PRODUCTION CSG: SIZE 4 1/2 FEET 4906  
NAME AND P.O. BOX 1197 SURFACE CASING: SIZE 8 5/8 FEET 265  
ADDRESS BILLINGS MT 59103

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A  
OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR MURFIN LICENSE NUMBER 30606  
ADDRESS 250 N WATER, STE 300, WICHITA, KS 67202

COMPANY TO PLUG AT: HOUR: 1:00pm DAY: 15 MONTH: 4 YEAR: 98

PLUGGING PROPOSAL RECEIVED FROM  
(COMPANY NAME) PAUL BRAUER (PHONE) (316)272-4931

WERE: Pump 300 lbs hulls, 25 sx cement, gell spacer, 100 SX pressure 8 5/8 to 500 lbs, pump 50 sx if needed. DV@2300 W/300sx PLUGGING PROPOSAL RECEIVED BY Kevin Strube

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART  NONE

OPERATIONS COMPLETED: HOUR: 2:30pm DAY: 15 MONTH: 4 YEAR: 98

ACTUAL PLUGGING REPORT Allied pumped down 8 5/8 x 5 1/2 annulas 5 SX @ 300#. Went down 4 1/2 w/ 200# Hulls ahead w/100# hulls mixed in cement, pumped 25sx cement 11 SX GEL 100sx cement Max PSI 1000#. Shut in @ 500#.

REMARKS: Used 60/40 Pozmix 6% gel by Allied No casing recovery

I (DID/xxxxxxx) OBSERVE THIS PLUGGING.

SIGNED Kevin D Strube  
(TECHNICIAN)

FORM CP-2/3

INVOICED  
DATE 4-21-98  
INV. NO. 50375  
4-15 JUN 17 1998