

5 040367

11-20-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 5-17-60 15-169-00188-00-01

NE SE SW, SEC. 32, T 14 S, R 2 W/EX

990 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6306

Lease Name Haag Well # 1

Operator: Tom Brown Construction

County Saline 105.59

Name & Address 240 Cole Street

Well Total Depth 3249 feet

Lindsborg, KS 67456

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 287

Abandoned Oil Well Gas Well Input Well SWD Well X D&A

Other well as hereinafter indicated

Plugging Contractor Tom Brown License Number 6306

Address Lindsborg, KS

Company to plug at: Hour: 9:00am Day: 20 Month: 11 Year: 1987

Plugging proposal received from Ralph Walker

(company name) Tom Brown Construction (phone)

work: Packer stuck in hole @2470 w/2" to surface. Pump through 2" and spot 50 sxs cement on bottom. 50 sxs slurry on top of packer to surface. 75 sxs cement in 10 3/4" and 7" annulus.

RECEIVED
STATE CORPORATION COMMISSION

NOV 23 1987

Plugging Proposal Received by Ralph Tittle (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:15pm Day: 20 Month: 11 Year: 1987

ACTUAL PLUGGING REPORT Packer stuck in hole @2470. Pumped 50 sxs cement through 2" and 1 sack chloride and displaced to bottom. Pumped 92 sxs into 5 1/2" and tubing annulus and annulus of 10 3/4" and 7". Max pressure 300#. Shut in. Will cut casing off 4' below surface. If cement went down will refill to surface with redimix. 7" in hole with 300 sxs--cement to 1400. 5 1/2" liner w/200 sxs--cement to surface.

Remarks: United Cementing Co. #0906
(If additional description is necessary, use BACK of this form.)

INVOICED

(If applicable) observe this plugging.

DATE 12-287

Signed Ralph Tittle (TECHNICIAN)

INV. NO. 19020

11-20