

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - Plugging Section
200 Colorado Derby Building
Wichita, Kansas 67202

AUG 9 1991
08 20 - 91
CONSERVATION DIVISION
Wichita, Kansas

API NUMBER: 15-169-20,182-00-00

C S/2 S/2 SW, SECTION 31 TOWNSHIP 14 RANGE 2W

OPERATOR LICENSE # 5120 330 FEET FROM S SECTION LINE
3960 FEET FROM E SECTION LINE

OPERATOR Range Oil Company, Inc.
NAME & 125 N. Market, #1120
ADDRESS Wichita, KS 67202

LEASE NAME: Caywood #3
COUNTY: Saline

WELL TOTAL DEPTH: 3320' 107.90

PIPE: 4-1/2" @ 3319'/100 sx

SURFACE CASING: 8-5/8" @ 217'

ABANDONED OIL WELL GAS WELL INPUT WELL SLD D&A

OTHER WELL AS HEREINAFTER INDICATED: _____

PLUGGING CONTRACTOR: Val Energy, Inc.
ADDRESS: Box 322, Haysville, KS 67060 LICENSE: 5822

COMPANY TO PLUG AT: HOUR: am DAY: 1 MONTH: 8 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Todd Allam

COMPANY NAME: Val Energy PHONE: 316-522-1560

WERE: Sand to 3175' - cap w/5 sx cmt - shoot pipe & pull -
set bridge @ 275' - slurry mix from 275'-0.

PLUGGING PROPOSAL RECEIVED BY: District #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL () PART () NONE ()

COMPLETED: HOUR: 10:00a DAY: 1 MONTH: 8 YEAR: 1991

ACTUAL PLUGGING REPORT:

Sanded to 3175' - capped w/5 sx cmt - shot pipe and
pulled - set bridge @ 275' - cmt slurry mix from 275'
to 0 - it took estimated 3-3/4 cu yds slurry cmt.
Perfs 3225-27' - Salina Concrete Products (10 sx
cmt/yd)

REMARKS: Recovered 534' of 4-1/2"

I DID OBSERVE THIS PLUGGING.

INVOICED
DATE 9-5-91
INV. NO. 32959

R. Phil Worley
R. Phil Worley (AGENT)

DW