

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - Plugging Section  
200 Colorado Derby Building  
Wichita, Kansas 67202

AUG 9 A 1991  
08-20-91  
CONSERVATION DIVISION  
Wichita, Kansas

API NUMBER: 15-169-20,146-00-00-20,361

SE SW NW, SECTION 31 TOWNSHIP 14 RANGE 2W

OPERATOR LICENSE # 5120 2970 FEET FROM S SECTION LINE  
4290 FEET FROM E SECTION LINE

OPERATOR Range Oil Company, Inc.  
NAME & 125 N. Market, #1120  
ADDRESS Wichita, KS 67202

LEASE NAME: Miller "B" #2  
COUNTY: Saline

WELL TOTAL DEPTH: 3300' 107.25

PIPE: 4-1/2" @ 3299'/75 SX

SURFACE CASING: 8-5/8" @ 207'

ABANDONED OIL WELL  GAS WELL  INPUT WELL D-20,361 SMD  D&A

OTHER WELL AS HEREINAFTER INDICATED: \_\_\_\_\_

PLUGGING CONTRACTOR: Val Energy, Inc.  
ADDRESS: Box 322, Haysville, KS 67060 LICENSE: 5822

COMPANY TO PLUG AT: HOUR: pm DAY: 2 MONTH: 8 YR: 1991

PLUGGING PROPOSAL RECEIVED FROM: Todd Allam

COMPANY NAME: Val Energy PHONE: 316-522-1560

WERE: Gravel to 3000' - cap w/5 sx cmt - shoot pipe - bail to 275 - set bridge - slurry mix 275' to surf.

PLUGGING PROPOSAL RECEIVED BY: District #2

PLUGGING OPERATIONS ATTENDED BY AGENT? ALL (  ) PART (  ) NONE (  )

COMPLETED: HOUR: 1:45p DAY: 2 MONTH: 8 YEAR: 1991

ACTUAL PLUGGING REPORT:

Gravel to 3000' - capped w/5 sx cmt - shot pipe - bailed to 275' - set solid bridge - slurry mix (10% sand) from 275' to surf - used 4 yds.

Perfs 3055-3110'

REMARKS: Salina Concrete Products Rec. 422' of 4-1/2"

I DID OBSERVE THIS PLUGGING.

**INVOICED**

DATE 9-5-91

INV. NO. 32960

R. Phil Worley  
R. Phil Worley (AGENT)

DW