

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-169- 20,104-00-00

200 Colorado Derby Bldg.  
Wichita, KS 67202

Operator's Full Name Range Oil Company, Inc.

Complete Address 240 Page Court, 220 W. Douglas, Wichita, Kansas 67202

Lease Name Weller Well No. 1

Location C E 1/2 NW Sec. 33 Twp. 14 Rge. 2 (~~East~~) (West)

County Saline Total Depth 3250'

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Voth Casing Pulling and United Cementing Co.

Address 715 S. A. Arkansas City, Kansas 67005 License No. 684

Operation Completed: Hour: 4:00 PM Day: 11 Month: September Year: 1981

Plugging Operations attended by Agent? All  Part  None

The above well was plugged as follows: 8 3/4" - 210' - 170 sacks 4 1/2" - 3289' - 100 sacks PBTD - 3280  
Per F 3252-57'

Hole Filled with sand to 3200' and cemented with 4 sacks.  
Hole squeezed with 4 sacks hulls, 20 sacks gel, and  
100 sacks cement pumped into 8 3/8" surface casing.  
2680' of 5 1/2" casing recovered  
Pumped hulls and gel and gel started coming up around the  
well about 20' away. Pump 50 sacks cement and cement  
started coming up. Waited 2 hours and pumped 30 sacks  
cement with little returns. Should have 300' of cement in  
hole.

09-14-81

I hereby certify that the above well was plugged as herein stated.

Signed: Arthur D. Palmer  
Conservation Division Agent

DATE 10/6/81  
FILE NO. 7822W