

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15-119-20097-00-00 (of this well)

Operator's Full Name Gear Petroleum Company  
Complete Address 300 Sutton Place, Wichita, Kansas 67202  
Lease Name Redden Well No. 1-B  
Location SE SE SE Sec. 36 Twp. 16 Rge. 2 (E)    (W) X  
County Saline Total Depth 2780'  
Abandoned Oil Well    Gas Well    Input Well    SWD Well    D & A X  
Other well as hereafter indicated   

Plugging Contractor Berentz Drilling Company  
Address Box 428, Eureka, Kansas License No.     
Operation Completed: Hour 3 PM Day 10 Month November Year 1971

The above well was plugged as follows: 8 5/8" - 166' - 5.1 @ 172' - cement circulated  
Hole Filled with mud to 160'. Plug and 1/2 sack hulls pushed to  
160' and hole cemented with 25 sacks cement. Hole Filled with  
mud to 40'. 1/2 sack hulls and plug pushed to 40' and  
hole cemented to base of cellar with 10 sacks cement.  
Rathole bridged and cemented with 2 sacks.

11-13-1971

I hereby certify that the above well was plugged as herein stated.

Signed: Alvin J. Bonar  
Well Plugging Supervisor

RECORDED  
11-17-71  
INV. NO. 0874W

15-169-20097-00-00

# LOG OF WELL

Redden #1-B  
SE SE SE  
Section 36-16S-2W  
Saline County, Kansas

OPERATOR: Gear Petroleum Co.

CONTRACTOR: Berentz Drilling Co.

Commenced with rotary: 11-5-79

Completed with rotary: 11-10-79

Casing: 8 5/8" -- 172' cemented with 125 sacks

|                     |              |
|---------------------|--------------|
| Soil                | 3'           |
| Shale & Lime        | 95'          |
| Lime & Shale        | 160'         |
| Lime & Shale Strks. | 470'         |
| Lime & Shale        | 1220'        |
| Shale & Lime        | 1844'        |
| Shale & Lime & Sand | 2236'        |
| Lime Lansing KC     | 2656'        |
| Shale & Lime        | 2769'        |
| Lime Miss.          | 2780' R.T.D. |

11-13-1979