

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-169-20, 171-00-00

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name Gear Petroleum Company, Inc.

Complete Address 300 Sutton Place, Wichita, Kansas 67262

Lease Name O/sson Well No. 1-22

Location SE SW NE Sec. 22 Twp. 16 Rge. 2 (~~East~~) (West)

County Saline Total Depth 3590'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated _____

Plugging Contractor Range Drilling Co, Inc. and Allied Cementing Co, Inc.

Address 240 Page Court, 220 W. Douglas, Wichita, Kansas License No. _____

Operation Completed: Hour: 12:00 Midnight Day: 16 Month: April Year: 19 82

Plugging Operations attended by Agent?: All Part _____ None _____

The above well was plugged as follows:

Hole circulated and filled with mud. 40 sacks cement pumped through drill pipe at 420'. 50 sacks cement pumped through drill pipe at 270'. Hole filled with mud to 40'. Plug and 1/2 sack balls pushed to 40' and hole cemented to base of cellar with 10 sacks cement. Rathole cemented with 10 sacks cement. Cement used 50/50 Pozmix w/4% gel and 3% c.c.

Orders by Marian Schmidt:

Amount of Surface Casing: 8 5/8" - 288' 200 sacks Cement 3% c.c.

I hereby certify that the above plugging instructions were given as herein stated.

Signed: [Signature]
Conservation Division Agent

I hereby state that I was not present while the above well was being plugged, however, to the best of my knowledge and belief it was plugged as herein stated. A full account for my not being present is as follows:

Signed: _____
Conservation Division Agent

4-28-82
64-W