

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-21740-00-00
Spot: NWSWNESW Sec/Twnshp/Rge: 3-22S-19E
1820 feet from S Section Line, 3890 feet from E Section Line
Lease Name: BUCHANAN Well #: 8181
County: ANDERSON Total Vertical Depth: 843 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.25	50		
PROD 2		825		

Well Type: EOR UIC Docket No: E09179.4 Date/Time to Plug: 11/14/2011 2:00 PM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Wash work string to bottom, cement to surface. Pull work string out, tie on to well, and squeeze cement into formation until desired pressure is achieved. Cut well off 3' below ground level, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 11/14/2011 2:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran work string to TD, circulated portland cement to surface, pulled pipe out, topped off well, hooked on to casing and squeezed cement into well, shut in at 500 psi used 50 sacks cement.

Perfs:

Top	Bot	Thru	Comments
800	816		SQUIRREL

RECEIVED

JAN 13 2012 JA

KCC Chanute Dist. #3

RECEIVED

JAN 20 2012

Remarks:

Plugged through: TBG

KCC WICHITA

District: 03

Signed


(TECHNICIAN)

1/25/12