

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-21419-00-00  
Spot: SWSENE Sec/Twnshp/Rge: 3-22S-19E  
1599 feet from S Section Line, 3163 feet from E Section Line  
Lease Name: BUCHANAN Well #: 181  
County: ANDERSON Total Vertical Depth: 865 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.25	20		
PROD	2.5	861		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/16/2011 12:00 PM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Revd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Wash work string to bottom, cement to surface. Pull work string out, tie on to well, and squeeze cement into formation until desired pressure is achieved. Cut well off 3' below ground level, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE  
Date/Time Plugging Completed: 11/16/2011 12:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor hooked up to casing, pumped water to establish flow rate, squeezed well with 45 sacks portland cement, shut in a 1000 psi.

Perfs:

Top	Bot	Thru	Comments
818	849		SQUIRRELL

RECEIVED

JAN 13 2012

KCC Chanute Dist. #3

JA

RECEIVED

JAN 20 2012

KCC WICHITA

Remarks:

Plugged through: CSG

District: 03

Signed

John Almond  
(TECHNICIAN)

1/25/12