

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-20685-00-00  
Spot: SWNENWSW Sec/Twnshp/Rge: 3-22S-19E  
2155 feet from S Section Line, 4618 feet from E Section Line  
Lease Name: BUCHANAN Well #: 278  
County: ANDERSON Total Vertical Depth: 866 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.25	18		
PROD	2.5	861		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/15/2011 12:00 PM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface, and squeeze cement until desired pressure is achieved. Cut off pipe 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE  
Date/Time Plugging Completed: 11/15/2011 12:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran work string to TD, circulated cement to surface, pulled pipe out, topped off well, hooked up to casing and squeezed cement into well, shut in at 1400 psi used 45 sacks cement.

Perfs:

Top	Bot	Thru	Comments
842	849		

RECEIVED

JAN 13 2012 JA

KCC Chanute Dist. #3

RECEIVED

JAN 20 2012

Remarks:

KCC WICHITA

Plugged through: TBG

District: 03

Signed

John Almond  
(TECHNICIAN)

✓ 1/25/12