

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-21106-00-00
Spot: NESENWSW Sec/Twnshp/Rge: 3-22S-19E
1706 feet from S Section Line, 4176 feet from E Section Line
Lease Name: BUCHANAN Well #: 280
County: ANDERSON Total Vertical Depth: 853 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| SURF | 7 | 25 | | |
| PROD | 2.5 | 846 | | |

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2011 12:00 PM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Wash work string to bottom, cement to surface. Pull work string out, tie to well, and squeeze cement into formation until desired pressure is achieved. Cut well off 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 11/14/2011 12:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran work string to TD, circulated portland cement to surface, pulled pipe out, hooked on to casing and squeezed cement, shut in at 600 psi used 65 sacks cement.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 820 | 840 | | |

RECEIVED

JAN 18 2012 JA

KCC Chanute Dist. #3

RECEIVED

JAN 20 2012

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)