

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-21420-00-00
Spot: SWSENWSW Sec/Twnshp/Rge: 3-22S-19E
1497 feet from S Section Line, 4408 feet from E Section Line
Lease Name: BUCHANAN Well #: 281
County: ANDERSON Total Vertical Depth: 863 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	20		
PROD	2.875	860		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/14/2011 2:00 PM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface, and squeeze cement until desired pressure is achieved. Cut off pipe 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 11/14/2011 2:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran work string to TD, circulated portland cement to surface, pulled pipe out, topped off well, hooked to casing and squeezed cement into well, shut in at 500 psi, used 57 sacks cement

Perfs:

Top	Bot	Thru	Comments
828	838		

RECEIVED

JAN 13 2012 JA

KCC Chanute Dist. #3

RECEIVED

JAN 20 2012

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)