

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-02004-00-00  
Spot: SWNWNESEW Sec/Twnshp/Rge: 3-22S-19E  
2099 feet from S Section Line, 3659 feet from E Section Line  
Lease Name: BUCHANAN Well #: 6  
County: ANDERSON Total Vertical Depth: 890 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF		10		
PROD		45		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/16/2011 12:00 PM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Wash work string to bottom, cement to surface. Pull work string out, tie to well, and squeeze cement into formation until desired pressure is achieved. Cut well off 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE  
Date/Time Plugging Completed: 11/16/2011 12:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran work string to TD, circulated portland cement to surface, pulled pipe out, topped off well, hooked on to casing squeezed cement into well, blew hole into 4.5 casing, washed down backside and circulated to surface, built damn around well, filled casing and backside with portland cement, used 122 sacks to plug well.

Perfs:

RECEIVED

JAN 13 2012 JA

KCC Chanute Dist. #3

RECEIVED

JAN 20 2012

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

  
(TECHNICIAN)