

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20572-00-00
Spot: NWSENE Sec/Twnshp/Rge: 34-21S-19E
4310 feet from S Section Line, 380 feet from E Section Line
Lease Name: KELLSTADT Well #: 8177
County: ANDERSON Total Vertical Depth: 843 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	25		
PROD	2	825		

Well Type: EOR UIC Docket No: E11406.23 Date/Time to Plug: 11/15/2011 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string out, tie onto well, and squeeze cement until desired pressure is achieved. Cut pipe off 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2011 12:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran work string to TD, circulated portland cement to surface, pulled pipe out, topped off well, hooked to casing and squeezed cement into well, shut in at 700 psi, used 30 sacks cement.

Perfs:

Top	Bot	Thru	Comments
825	843		SQUIRREL

RECEIVED
JAN 20 2012

RECEIVED
JAN 18 2012
JA

KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

KCC WICHITA

District: 03

Signed

John Almond
(TECHNICIAN)

1/25/12