

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-22583-00-00
Spot: E2E2SWNW Sec/Twnshp/Rge: 22-22S-19E
3300 feet from S Section Line, 4240 feet from E Section Line
Lease Name: COOPER Well #: 19
County: ANDERSON Total Vertical Depth: 870 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	20		
PROD	2.875	867		90 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/03/2011 12:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: RUN WORKSTRING TO BOTTOM, CEMENT TO SURFACE. TIE TO 2.875" SQUEEZE CEMENT UNTIL DESIRED AMOUNT OF CEMENT AND PRESSURE IS ACHIEVED. DIG OUT PIPE 3 FOOT BELOW SURFACE, CUT, CAP AND BACKFILL.

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE
Date/Time Plugging Completed: 11/03/2011 12:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran work string to TD, circulated portland cement to surface, pulled pipe out, topped off well, hooked on casing and squeezed, shut in well at 500 psi used 85 sacks cement to plug.

Perfs:

Top	Bot	Thru	Comments
839	849		

RECEIVED

JAN 12 2012 JA

KCC Chanute Dist. #3

RECEIVED

JAN 20 2012

Remarks:

Plugged through: TBG

KCC WICHITA

District: 03

Signed


(TECHNICIAN)