

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-01976-00-00
Spot: SWNWNENE Sec/Twnshp/Rge: 34-21S-19E
4658 feet from S Section Line, 1000 feet from E Section Line
Lease Name: KELLSTADT Well #: 25
County: ANDERSON Total Vertical Depth: 821 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	20		7 SX
PROD	2.875	821		88 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/12/2011 12:00 PM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Wash work string to bottom, cement to surface. Pull work string out, tie on to well, and squeeze cement into formation until desired pressure is achieved. Cut well off 3' below ground level, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE
Date/Time Plugging Completed: 12/12/2011 12:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor perforated casing at 555', contractor ran work string to TD, circulated portland cement to surface, pulled pipe out, topped off well, hooked on casing and squeezed cement into well, shut in well at 350 psi, used 140 sacks cement.

Perfs:

Top	Bot	Thru	Comments
802	806		SQUIRREL

RECEIVED

JAN 13 2012 JA

KCC Chanute Dist. #3

RECEIVED

JAN 20 2012

Remarks:

Plugged through: TBG

KCC WICHITA

District: 03

Signed


(TECHNICIAN)

✓ 1/25/12