

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20668-00-00
Spot: NENWNENE Sec/Twnshp/Rge: 34-21S-19E
4975 feet from S Section Line, 792 feet from E Section Line
Lease Name: KELLSTADT Well #: 178
County: ANDERSON Total Vertical Depth: 821 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	20		7 SX
PROD	2.875	821		88 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/04/2011 10:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Wash work string to bottom, cement to surface. Pull work string out, tie on to well, and squeeze cement into formation until desired pressure is achieved. Cut well off 3' below ground level, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE
Date/Time Plugging Completed: 11/04/2011 10:00 AM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran work string to TD, circulated portland cement to surface, pulled pipe out, topped off well, hooked to casing and squeezed cement into well, shut in at 600 psi, used 63 sacks cement.

Perfs:

Top	Bot	Thru	Comments
802	806		

RECEIVED
JAN 20 2012
KCC WICHITA

RECEIVED
JAN 13 2012 JA
KCC Chanute Dist #3

Remarks:

Plugged through: TBG

District: 03

Signed _____

(TECHNICIAN)

✓ 1/25/12