

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20669-00-00
Spot: NWNWNENE Sec/Twnshp/Rge: 34-21S-19E
5074 feet from S Section Line, 1308 feet from E Section Line
Lease Name: KELLSTADT Well #: 278
County: ANDERSON Total Vertical Depth: 821 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	20		7 SX
PROD	2.875	821		88 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/16/2011 10:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Wash work string to bottom, cement to surface. Pull work string out, tie on to well, and squeeze cement into formation until desired pressure is achieved. Cut well off 3' below ground level, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 11/16/2011 10:00 AM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran work string to TD, circulated portland cement to surface, pulled pipe out, topped off well, hooked on to casing and squeezed cement into well, shut in at 650 psi, used 40 sacks cement.

Perfs:

Top	Bot	Thru	Comments
802	806		

RECEIVED

JAN 13 2012 JA

KCC Chanute Dist. #3

RECEIVED

JAN 20 2012

Remarks:

KCC WICHITA

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)