

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-21178-00-00  
Spot: SWNWNWNE Sec/Twnshp/Rge: 34-21S-19E  
4780 feet from S Section Line, 2568 feet from E Section Line  
Lease Name: KELLSTADT Well #: 380  
County: ANDERSON Total Vertical Depth: 878 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	20		
PROD	2.5	840		

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/17/2011 10:00 AM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string, tie onto well and squeeze cement until desired pressure is achieved. Cut off pipe 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE  
Date/Time Plugging Completed: 11/17/2011 10:00 AM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran work string to TD, circulated portland cement to surface, pulled pipe out, topped off well, hooked on to casing and squeezed cement into well, shut in at 800 psi, used 68 sacks cement.

Perfs:

Top	Bot	Thru	Comments
840	878		SQUIRREL

RECEIVED  
JAN 13 2012 JA  
KCC Chanute Dist. #3

RECEIVED  
JAN 20 2012  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

John Almond  
(TECHNICIAN)

✓ 1/25/12