

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20518-00-01
Spot: NWNWNE Sec/Twnshp/Rge: 34-21S-19E
4720 feet from S Section Line, 2310 feet from E Section Line
Lease Name: KELLSTADT Well #: 476
County: ANDERSON Total Vertical Depth: 866 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| SURF | 7 | 30 | | |
| PROD | 2.5 | 842 | | |

Well Type: EOR UIC Docket No: E11406.17 Date/Time to Plug: 11/04/2011 10:00 AM
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string, tie onto well and squeeze cement until desired pressure is achieved. Cut off pipe 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE
Date/Time Plugging Completed: 11/04/2011 10:00 AM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran work string to TD, circulated portland cement to surface, pulled pipe out, hooked to casing and squeezed cement into well, shut in at 700 psi, used 45 sacks cement.

Perfs:

| Top | Bot | Thru | Comments |
|-----|-----|------|----------|
| 842 | 866 | | SQUIREL |

RECEIVED

JAN 13 2012

JA

KCC Chanute Dist. #3

RECEIVED

JAN 20 2012

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)

1/25/12