

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20253-00-00
Spot: NENENWNE Sec/Twnshp/Rge: 34-21S-19E
5066 feet from S Section Line, 1571 feet from E Section Line
Lease Name: KELLSTADT Well #: 34P
County: ANDERSON Total Vertical Depth: 874 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	40		
PROD	2.5	869		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/15/2011 2:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string, tie onto well and squeeze cement until desired pressure is achieved. Cut off pipe 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2011 2:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran work string to TD, circulated portland cement to surface, pulled pipe out, topped off well, washed pipe down backside to 40' circulated cement to surface, hooked on to casing and squeezed cement into well, shut in at 600 psi, used 66 sacks cement.

Perfs:

Top	Bot	Thru	Comments
839	863		SQUIRREL

RECEIVED
JAN 20 2012
KCC WICHITA

RECEIVED
JAN 13 2012 JA
KCC Chanute Dist. #3

Remarks:

Plugged through: TBG

District: 03

Signed

John Almond
(TECHNICIAN)

✓ 1/25/12