



15-169-00402-00-01

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 16 1973
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Francis M. Raymond of Raymond Oil Company has this
date requested permission to plug the following described well:

Mr. Raymond Oil Company guarantees payment of the plugging fee.

Operator's full Name: Raymond Oil Company, Inc.

Complete Address: 200 W. Douglas, Wichita, Kansas 67202

Lease Name: Jarvis Well No. # 2-Twin

Location: SE NE SW Sec. 7 Twp. 14 Rge. 2 (E)(W) W

County: Saline Total Depth 3176 Oil Well

Gas Well Input Well SWD Well X D & A Lost Hole

Mr. Mike Wassinger was instructed to plug the well as follows:

8 5/8" csg. 150' Cwc.

Sanded hole back to 3150' & dumped 5 sax cement with dump bailer.

Pulled pipe. Squeezed well with 3 sax hulls, 20 sax mud, & 90 sax

cement with Allied Cementing Company's pump truck, cementing from

330' to base of cellar.

Very truly yours,

Don Truman
Conservation Division Agent