



JOHN ANDERSON, Jr. Governor  
 RICHARD C. BYRD Chairman  
 ALVIN F. GRAUERHOLZ Commissioner  
 HARRY G. WILES Commissioner  
 RAYMOND B. HARVEY Secretary  
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission  
 CONSERVATION DIVISION  
 (Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

March 31, 1963

J. P. Roberts  
 Assistant Director  
 500 Insurance Building  
 212 North Market  
 Wichita 2, Kansas

RECEIVED  
 STATE CORPORATION COMMISSION

APR 9 1963

CONSERVATION DIVISION  
 Wichita, Kansas

Dear Sir:

Mr. Troy Smith of Kent Well Servicing Co. has this

date requested permission to plug the following described well:

Mr. Smith guarantees payment of the plugging fee.

Operator's full Name: Donald T. Ingling

Complete Address: 615 First Nat'l Bldg., Wichita 2, Kansas

Lease Name: Wessling Well No. 1

Location: C SW NW Sec. 5 Twp. 14 Rge. 2 (X) (W) X

County Saline Total Depth 3203 Oil Well         

Gas Well          Input Well          SWD Well          D & A X Lost Hole         

Mr. Smith was instructed to plug the well as follows:

Fill hole with sand to 3190' and cement with 4 sacks.

Fill hole with mud to 200'. Set rock bridge from 200' to

190' and cement with 20 sacks. Fill hole with mud to 40'.

Set rock bridge from 40' to 35' and cap hole with 10 sacks

cement.

Very truly yours,

*[Signature]*  
 Conservation Division Agent