

State of Kansas



15-169-19051-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

RECEIVED
STATE CORPORATION COMMISSION

JUN 28 1967

CONSERVATION DIVISION
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

June 23, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Bert Self of Self Casing Pulling Co. has this date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Hollar Oil Company

Complete Address: Box 620, Mc Pherson, Kansas 67460

Lease Name: Krauss Well No. B-1

Location: C SW SE Sec. 23 Twp. 15 Rge. 2 (E)(W) X

County Saline Total Depth 2729' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Self was instructed to plug the well as follows:

Fill hole with sand to 2700' and cement with 5 sacks.

Fill hole with mud to 160'. Set rock bridge from 160' to 150' and

cement with 20 sacks. Fill hole with mud to 40'. Set rock bridge from

40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent