



15-169-20014-00-00

ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

DEC 21 1967
State Corporation Commission

12-21-67

CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

December 12, 1967

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co., Inc this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Frank J. Elack

Complete Address: Box 150, Mc Pherson, Kansas 67460

Lease Name: Hubbard Well No. 3

Location: C NE SW Sec. 23 Twp. 15 Rge. 2 (E)(W) X

County: Saline Total Depth 2725' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 2700' and cement with 5 sacks.

Fill hole with mud to 135'. Set rock bridge from 135' to 125' and

cement hole with 25 sacks cement. Fill hole with mud to 40'. Set rock

bridge from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent