



15-169-30029-00-00

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JOHN C. WOELK Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

June 12, 1966

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Bill Makely of Melland Drilling Co., Inc. has this  
date requested permission to plug the following described well:

Mr. Makely guarantees payment of the plugging fee.

Operator's full Name: Hollar Oil Company

Complete Address: 1117 Wichita Plaza Bldg., Wichita, Kansas

Lease Name: Ringquist Well No. 1

Location: C E/2 W/2 SE Sec. 14 Twp. 15 Rge. 2 ☒ (W) ☐ X

County Saline Total Depth 2767' Oil Well ☐

Gas Well ☐ Input Well ☐ SWD Well ☐ D & A ☒ Lost Hole ☐

Mr. Makely was instructed to plug the well as follows:

Fill hole with mud to 130'. Push plug and  $\frac{1}{2}$  sack hulls to 130' and  
cement hole with 20 sacks through drill pipe. Fill hole with mud to  
40'. Push plug and  $\frac{1}{2}$  sack hulls to 40' and cap hole with 10 sacks  
cement. Bridge rathole, and cement with 2 sacks.

Very truly yours,

Stilwell J. Leonard  
Conservation Division Agent