



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

RECEIVED
CORPORATION COMMISSION
JUL 22 1968

State Corporation Commission

CONSERVATION DIVISION
Wichita, Kansas

CONSERVATION DIVISION
(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

July 16, 1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. H. G. Pankratz of H-30, Inc. has this

date requested permission to plug the following described well:

Mr. Pankratz guarantees payment of the plugging fee.

Operator's full Name: H-30, Inc. et al

Complete Address: 200 N. Main, Wichita, Kansas 67202

Lease Name: Bachofer Well No. 2

Location: C NE NE Sec. 14 Twp. 15 Rge. 2 (W) X

County: Saline Total Depth 3749' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Pankratz was instructed to plug the well as follows:

Fill hole with mud to 200'. Push plug and 1/4 sack hulls to 200' and
cement hole with 20 sacks through drill pipe. Fill hole with mud to
40'. Push plug and 1/2 sack hulls to 40' and cap hole with 10 sacks
cement. Bridge rathole and cement with 2 sacks.

Very truly yours,

William J. Johnson
Conservation Division Agent