

State of Kansas



15-169-30003-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

FILED  
STATE CORPORATION COMMISSION  
AUG 27 1966  
08-29-66  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Self of Hollar Oil Company has this  
date requested permission to plug the following described well:

Mr. Self guarantees payment of the plugging fee.

Operator's full Name: Hollar Oil Company

Complete Address: Box 620 McPhefson, Kansas

Lease Name: Belander Well No. # 1

Location: C S/2 1/4 SW Sec. 13 Twp. 15 Rge. 2 / (E) (W)

County Saline Total Depth 2745' Oil Well X

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Self was instructed to plug the well as follows:

10"-139'-Circulated w/cement, 7"-2743'-Cemented, Sandhole to 2730'.  
7 Saz. cement 2730' to 2700'. Mud 2700' to 150'. Bridge 150' to 140'.  
35 Saz. cement 140' to 70'. Mud 70' to 40'. Bridge 40' to 30'.  
15 Saz. cement 30' to 0.

Very truly yours,

[Signature]  
Conservation Division Agent