

State of Kansas



15-169-19025-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
1-17-67  
JAN 17 1967

CONSERVATION DIVISION  
Wichita, Kansas

January 7, 1967

WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Noel Knight of Knight Casino Pulling Co. has this  
date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: H-30, Inc.

Complete Address: 200 North Main, Wichita, Kansas

Lease Name: Caywood Well No. 1

Location: C W/4 NE/4 Sec. 6 Twp. 15 Rge. 2 (E) (W)

County Saline Total Depth 3233' Oil Well

Gas Well  Input Well  SWD Well  D & A  Lost Hole

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3230' and cement with 3 sacks.

Fill hole with mud to 200'. Set rock bridge from 200' to 190' and

cement hole with 20 sacks. Fill hole with mud to 40'. Set rock bridge

from 40' to 30' and cap hole with 10 sacks cement.

Very truly yours,

Conservation Division Agent