

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20256-00-00
Spot: NWSENE Sec/Twnshp/Rge: 34-21S-19E
4462 feet from S Section Line, 425 feet from E Section Line
Lease Name: KELLSTADT Well #: 36P
County: ANDERSON Total Vertical Depth: 821 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	20		7 SX
PROD	2.875	821		88 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/15/2011 10:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Wash work string to bottom, cement to surface. Pull work string out, tie on to well, and squeeze cement into formation until desired pressure is achieved. Cut well off 3' below ground level, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/15/2011 10:00 AM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran work string to TD, circulated portland cement to surface, pulled pipe out, topped off well, washed pipe down backside of casing to 210' circulated portland cement to surface, hooked on casing and squeezed cement into well, shut in at 650 psi, used 172 sacks cement.

Perfs:

Top	Bot	Thru	Comments
802	806		SQUIRREL

RECEIVED

JAN 13 2012

JA

KCC Chanute Dist. #3

RECEIVED

JAN 20 2012

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)