

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGIN  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-003-22211-00-00  
Spot: SESWSWNW Sec/Twnshp/Rge: 34-21S-19E  
2940 feet from S Section Line, 4680 feet from E Section Line  
Lease Name: KELLSTADT Well #: 183-P  
County: ANDERSON Total Vertical Depth: 821 feet

Operator License No.: 33097  
Op Name: SOUTHERN STAR CENTRAL GAS PIPE  
Address: 4700 HWY 56  
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	20		7 SX
PROD	2.875	821		88 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 11/18/2011 12:00 PM  
Plug Co. License No.: 34059 Plug Co. Name: HURRICANE SERVICES, INC.  
Proposal Revd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Wash work string to bottom, cement to surface. Pull work string out, tie on to well, and squeeze cement into formation until desired pressure is achieved. Cut well off 3' below ground level, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE  
Date/Time Plugging Completed: 11/18/2011 12:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Perfs:

Contractor ran work string to TD, circulated portland cement to surface, pulled pipe out, topped off well, hooked to casing and squeezed cement into well, shut in at 850 psi, used 50 sacks cement.

RECEIVED

JAN 13 2012 JA

KCC Chanute Dist. #3

RECEIVED  
JAN 20 2012

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

  
(TECHNICIAN)

✓ 1/20/12