

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20570-00-00
Spot: NWNEENE Sec/Twnshp/Rge: 34-21S-19E
5020 feet from S Section Line, 350 feet from E Section Line
Lease Name: KELLSTADT Well #: 6177
County: ANDERSON Total Vertical Depth: 882 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	7	25		10 SX
PROD	2	887		125 SX

Well Type: EOR UIC Docket No: E11406.21 Date/Time to Plug: 11/14/2011 10:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string out, tie onto well, and squeeze cement until desired pressure is achieved. Cut pipe off 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND Witness Type: NONE
Date/Time Plugging Completed: 11/14/2011 10:00 AM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran work string to TD, circulated portland cement to surface, pulled pipe out, topped off well, hooked to casing and squeezed cement into well, shut in at 600 psi, used 39 sacks cement.

Perfs:

Top	Bot	Thru	Comments
821	838		SQUIRREL

RECEIVED

JAN 18 2012 JA

KCC Chanute Dist. #3

RECEIVED
JAN 20 2012

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed


(TECHNICIAN)

✓ 1/25/12