

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20657-00-00
Spot: SESESESW Sec/Twnshp/Rge: 22-21S-19E
220 feet from S Section Line, 2420 feet from W Section Line
Lease Name: LYTLE Well #: 1
County: ANDERSON Total Vertical Depth: 765 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD 2		762		

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/18/2011 12:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface and squeeze cement until desired amount of pressure is achieved. Cut off pipe 3' below surface, cap and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 11/18/2011 10:00 AM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran work string to TD, circulated portland cement to surface, pulled work string out, topped off well. Hooked up to well and squeezed cement into casing, shut in at 850 psi. 39 sacks portland to plug well.

Perfs:

Top	Bot	Thru	Comments
732	740		

RECEIVED

JAN 12 2012 JA

KCC Chanute Dist. #3

RECEIVED

JAN 20 2012


Remarks:

Plugged through: TBG

KCC WICHITA

District: 03

Signed


(TECHNICIAN)

✓ 1/25/12