

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGIN
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-003-20670-00-00
Spot: NENWSENE Sec/Twnshp/Rge: 34-21S-19E
3834 feet from S Section Line, 750 feet from E Section Line
Lease Name: SUMMERS Well #: 178
County: ANDERSON Total Vertical Depth: 853 feet

Operator License No.: 33097
Op Name: SOUTHERN STAR CENTRAL GAS PIPE
Address: 4700 HWY 56
OWENSBORO, KY 42301

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	6.25	11		2 SX
PROD	2.5	851		90 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/04/2011 2:00 PM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: STERLING BARKER Company: SOUTHERN STAR Phone: (785) 448-4816

Proposed Plugging Method: Run work string to bottom, cement to surface. Pull work string, tie onto well and squeeze cement until desired pressure is achieved. Cut pipe off 3' below surface, cap, and backfill.

Plugging Proposal Received By: JOHN ALMOND WitnessType: NONE
Date/Time Plugging Completed: 11/04/2011 2:00 PM KCC Agent: JOHN ALMOND

Actual Plugging Report:

Contractor ran work string to TD, circulated portland cement to surface, pulled pipe out, topped off well, hooked to casing and squeezed cement into well, shut in at 450 psi, used 39 sacks cement.

Perfs:

Top	Bot	Thru	Comments
826	836		SQUIRREL

RECEIVED

JAN 13 2012 JA

KCC Chanute Dist #3

RECEIVED

JAN 20 2012

KCC WICHITA

Remarks:

Plugged through: TBG

District: 03

Signed

John Almond
(TECHNICIAN)

✓ 1/25/12