

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-135-21614-00-01
Spot: SESW Sec/Twnshp/Rge: 9-18S-26W
619 feet from S Section Line, 3225 feet from E Section Line
Lease Name: WHIPPLE I Well #: OWWO
County: NESS Total Vertical Depth: 4645 feet

Operator License No.: 5011
Op Name: VIKING RESOURCES, INC
Address: 400 N WOODLAWN ST, STE 18
WICHITA, KS 67208

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	221		WITH 150 SX CMT
PC		2030		WITH 370 SX CMT
PROD	4.5	4644	0	WITH 575 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 12/30/2011 9:00 AM
Plug Co. License No.: 32382 Plug Co. Name: SWIFT SERVICES, INC.
Proposal Rcvd. from: BILLY BRINEY Company: WHITETAIL CRUDE Phone: (316) 262-2502

Proposed Plugging Method: RUN TBG TO BOTTOM & SPOT 25 SX COMMON CMT W/3% CC. PULL TBG TO 2060' & CIRCULATE CMT. TIE ONTO BACKSIDE & PUMP CMT IF POSSIBLE

Plugging Proposal Received By: STEVE DURRANT Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 12/30/2011 3:00 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 4464' & SPOT 25 SX COMMON CMT W/3% CC. PULL TBG TO 2060'. PUMP 140 SX CMT & 400# HULLS. CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 20 SX CMT. TIED ONTO BACKSIDE & PUMPED 30 SX CMT. PRESSURED TO 500# & HELD.

Perfs:


Top	Bot	Thru	Comments
4384	4386		MARMATON

Remarks: USED 60/40 POZMIX 4% GEL BY SWIFT SERVICES.

Plugged through: TBG

District: 01

Signed



(TECHNICIAN)

RECEIVED
JAN 05 2012
KCC DODGE CITY

RECEIVED
JAN 23 2012
KCC WICHITA

Perf CP-2/3

1/25/12