

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-163-00723-00-00
Spot: S2S2SE Sec/Twnshp/Rge: 29-10S-20W
330 feet from S Section Line, 1320 feet from E Section Line
Lease Name: KELLER (THOMAS) Well #: 1
County: ROOKS Total Vertical Depth: 3764 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	163		105 SX
PROD	5.5	3762		100 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/05/2012 9:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KENT WILSON Company: MAI OIL Phone: (785) 483-1683

Proposed Plugging Method: Ordered 450 sx 60/40 pos 4% gel, 600# hulls, 10 sx gel Perforated @2200', 1675', and 925'.
Tubing shot off @3685'.
6-3-2002 Sqz 3215'-3338' w/300 sx, 3-6-2006 Sqz 977'-1163 w/250 sx

Plugging Proposal Received By: CASE MORRIS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 01/05/2012 1:00 PM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3670', pumped 10 sx gel followed by 50 sx cmt w/200#hulls
Pulled tubing to 2200', pumped 60 sx cmt w/150# hulls
Pulled tubing to 1665', pumped 80 sx cmt w/150# hulls
Pulled tubing to 945', circulated to surface w/ 119 sx cmt w/100# hulls
POOH. Topped off 5 1/2" w/50 sx cmt
Hooked to backside and pressured to 500 psi.

Perfs:

RECEIVED
JAN 24 2012
KCC WICHITA

Remarks: ALLIED CEMENTING #35199

Plugged through: TBG

District: 04

Signed

Pat Bedore
(TECHNICIAN)

CM

JAN 12 2012

Form CP-2/3

✓ 1/25/12