

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-051-00411-00-01
Spot: NWNWNW Sec/Twnshp/Rge: 17-11S-18W
4950 feet from S Section Line, 4950 feet from E Section Line
Lease Name: FRISBIE M Well #: 1F
County: ELLIS Total Vertical Depth: 3600 feet

Operator License No.: 9408
Op Name: TRANS PACIFIC OIL CORPORATION
Address: 100 S MAIN STE 200
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	1218		500 SX
PROD	5.5	3599		200 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 01/18/2012 12:00 PM
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC
Proposal Rcvd. from: KEN BUHLER Company: TRANS PACIFIC OIL CORP. Phone: (785) 483-1821

Proposed Plugging Method: Ordered- 675 sxs 60/40 poz mix, 4% gel, 500 # hulls
PBTD 3420'
CSG-leaks
PBTD -3420

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 01/18/2012 4:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Perf Tech Perfed @ 1850 & 1200"
Express Well Service Knocked out CIBP @ 2905.
Express RIH with tubing to 3200' Quality mixed & pumped 150 sxs cement with 300 # hulls mixed in.
Pulled tubing to 1850' Quality mixed & pumped 150sxs with 200 # Hulls mixed into circulate cement up 5-1/2" CSG.
Pulled tubing rigged to 5-1/2" CSG with a swedge & pumped 20 sxs to pressure, with 400 # P.I.P. & 300 # S.I.P.
Rigged to 8-5/8" CSG & pumped 1 sx to pressure with 1000 # P.I.P.

Perfs:

Top	Bot	Thru	Comments
3168	3393		
2931	3167		
0	0		Open ARB

RECEIVED
JAN 24 2012
1-24-12
KCC WICHITA

Remarks: QUALITY CEMENTING CO. TICKET # 665

Plugged through: TBG

District: 04

Signed _____

[Signature]
(TECHNICIAN)

CM

KCC

JAN 19 2012

HAYS

Form CP-2/3

1/25/12