

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-171-20847-00-00  
Spot: N2NWSESW Sec/Twnshp/Rge: 25-19S-31W  
1155 feet from S Section Line, 1650 feet from W Section Line  
Lease Name: DREW TRUST Well #: 14B-25-1931  
County: SCOTT Total Vertical Depth: 4800 feet

Operator License No.: 33476  
Op Name: FIML NATURAL RESOURCES, LLC  
Address: 410 17TH ST STE 900  
DENVER, CO 80202

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	375		WITH 240 SX CMT

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/10/2012 10:30 AM  
Plug Co. License No.: 33793 Plug Co. Name: H2 DRILLING LLC  
Proposal Rcvd. from: GARY DOKE Company: FIML NATURAL RESOURCES Phone: (303) 893-5073

Proposed Plugging Method: 1ST PLUG AT 2220' WITH 50 SX CMT. 2ND PLUG AT 1480' WITH 80 SX CMT. 3RD PLUG AT 740' WITH 40 SX CMT. 4TH PLUG AT 410' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: NONE  
Date/Time Plugging Completed: 01/10/2012 12:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

1ST PLUG AT 2220' WITH 50 SX CMT. 2ND PLUG AT 1480' WITH 80 SX CMT. 3RD PLUG AT 740' WITH 40 SX CMT. 4TH PLUG AT 410' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Perfs:

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: DP

District: 01

RECEIVED  
JAN 13 2012  
KCC DODGE CITY

Signed

Jack MacLuskey  
(TECHNICIAN)

RECEIVED  
JAN 23 2012  
KCC WICHITA

Form CP 29  
1/30/12