

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-025-20076-00-00
Spot: SWSWNESE Sec/Twnshp/Rge: 33-34S-22W
1370 feet from S Section Line, 1270 feet from E Section Line
Lease Name: ARNOLD Well #: 1-33
County: CLARK Total Vertical Depth: 5740 feet

Operator License No.: 34318
Op Name: BEREXCO LLC
Address: 2020 N. BRAMBLEWOOD
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5480		WITH 2 SX CMT
SURF	8.625	632		WITH 375 SX CMT
COND	20	73		
PROD	4.5	5739	2152	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/04/2012 2:00 PM
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.
Proposal Rcvd. from: BARRY WALTERS Company: ALLIANCE WELL SERVICE INC. Phone: (620) 672-9100

Proposed Plugging Method: SET CIBP @ 5480' WITH 2 SX CMT. PLUG AT 900' WITH 15 SX GEL & 50 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 300' WITH 40 SX CMT. PLUG AT 60' WITH 25 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 01/04/2012 4:30 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

CIBP @ 5480' WITH 2 SX CMT. 1ST PLUG AT 912' WITH 15 SX GEL & 50 SX CMT.
2ND PLUG AT 665' WITH 50 SX CMT. 3RD PLUG AT 315' WITH 40 SX CMT. 4TH
PLUG AT 60' WITH 25 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5550	5580		Mississippian
5538	5546		Morrow

Remarks: USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

District: 01

RECEIVED
JAN 05 2012
KCC DODGE CITY

Signed

Richard W. Lacey

RECEIVED
(TECHNICIAN)

JAN 23 2012

KCC WICHITA

Form CP-2/3

[Signature]
1/30/12