

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-163-30119-00-00  
Spot: SWNWNE Sec/Twnshp/Rge: 14-9S-16W  
4683 feet from S Section Line, 1279 feet from E Section Line  
Lease Name: BLANK Well #: 2  
County: ROOKS Total Vertical Depth: 3515 feet

Operator License No.: 30821  
Op Name: HITSCHMANN, CRAIG & RONDA DBA  
Address: PO BOX 308  
NATOMA, KS 67651

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	68		75 SX
PROD	5.5	3193		150 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: \_\_\_\_\_  
Plug Co. License No.: 32028 Plug Co. Name: CHITO'S WELL SERVICE, LLC  
Proposal Rcvd. from: CHITO'S WELL SERVICE, L Company: \_\_\_\_\_ Phone: (785) 737-3746

Proposed Plugging Method: Sqz @ 975' Production open hole completion from 3193' to 3476'. Ordered out 465 sx 60/40 poz mix 4 % gel w/ 500# hulls.

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/09/2012 4:00 PM KCC Agent: RICHARD WILLIAMS

Actual Plugging Report:

L K perforated 2 holes each @ 1650' & 1390', Ran tubing to 2549' hard bottom, unable to get below. Copeland Acid & Cement pumped 125 sx w/300# hulls, pulled tubing to 1380' & pumped 200 sx w/ 200# hulls, pulled tubing to 650' and pumped 100 sx circulated cement. P.T.O.H. topped casing off w/ 35 sx cement. Hooked up to backside and pumped 5 sx instant 300# blew hole in 8 5/8 surface pipe.

Perfs:

Top	Bot	Thru	Comments
3193	3476		

RECEIVED  
JAN 24 2012  
KCC WICHITA

Remarks:

Plugged through: TBG

District: 04

Signed Richard Williams  
(TECHNICIAN)

CM

Form CP-2/3

JAN 17 2012

✓ 1/30/12