

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-115-20746-00-00
Spot: NWSESW Sec/Twnshp/Rge: 6-21S-3E
1103 feet from S Section Line, 3674 feet from E Section Line
Lease Name: HEYLAND Well #: 1
County: MARION Total Vertical Depth: 2840 feet

Operator License No.: 5616

Op Name: NOAH, CALVIN

Address: 329 N BIRCH
VALLEY CENTER, KS 67147

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	204		100 SX
PROD	5.5	2837		75 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/13/2012 10:00 AM

Plug Co. License No.: 3038

Plug Co. Name: CYCLONE WELL SERVICE, INC.

Proposal Rcvd. from: CALVIN NOAH

Company:

Phone: (316) 755-0051

Proposed Plugging Method: AS PER KCC

Plugging Proposal Received By:

WitnessType: COMPLETE (100%)

Date/Time Plugging Completed: 01/17/2012 11:00 AM

KCC Agent: SHANE JONES

Actual Plugging Report:

Perfs:

1/12/12 CYCLONE WELL SERVICE LAID OUT WELL. THEY DROPPED SAND AND PERFORATED @255'. 1/13/12 CYCLONE WELL SERVICE TAGGED SAND @ 2770' AND CAPPED W/5 SX. THEY THEN RAN TUBING TO 250'. COPELAND TIED ON AND BROKE CIRCULATION WITH WATER. THEY THEN SWITCHED TO CEMENT, AND CIRCULATED 165 SX TO SURFACE AND SHUT IN. COPELAND TK #37859 165 SX 60/40 POS W/4% GEL. 1/17/12 I CHECKED TOP PLUG FINDING IT DOWN 15' ON BACKSIDE AND INSIDE CASING. CYCLONE OUT TO CUT OFF CASING AND BACK FILL HOLE. THEY WILL TAKE CARE OF TOPPING OFF WELL.

Top	Bot	Thru	Comments
2837	2840	OH	HUNTON OH


RECEIVED
JAN 25 2012
KCC WICHITA

Remarks:

Plugged through: TBG

District: 02

Signed



(TECHNICIAN)

Form CP-2/3

✓ 1/30/12

✓ JK