

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-21505-00-00
Spot: SWNESW Sec/Twnshp/Rge: 34-32S-42W
1659 feet from S Section Line, 3590 feet from E Section Line
Lease Name: GLADYS N Well #: 1-34B
County: MORTON Total Vertical Depth: 5066 feet

Operator License No.: 5003
Op Name: MCCOY PETROLEUM CORPORATION
Address: 8080 E CENTRAL STE 300
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	1414		WITH 200 SX CMT
COND	13.375	533		WITH 320 SX CMT
PC		2565		WITH 130 SX CMT
PROD	4.5	5056	1590	WITH 150 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 01/12/2012 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP CMT OVER EACH SET OF PERFS. LET CMT SET 2 HOURS AFTER CMT INTO TOP PERFS. TAG TOC. SHOT CASING & POH. RIH W/TBG TO 1440' & PUMP 15 SX GEL & 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 40' TO SURFACE.

Plugging Proposal Received By: JACK MACLASKEY Witness Type: NONE
Date/Time Plugging Completed: 01/12/2012 5:30 PM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

PUMPED 50 SX CMT OVER PERFS. LET SET 2 HOURS & TAGGED TOC @ 2810'. SANDED WELL BORE TO 2636' & TOPPED WITH 4 SX CMT. SHOT 4 1/2" CASING @ 1590' & POH. RIH W/TBG TO 1440'. PUMPED 100# HULLS, 15 SX GEL & 50 SX CMT. POH TO 480' & PUMPED 50 SX CMT. TOPPED WELL OFF WITH 20 SX CMT AT 40'.

Perfs:

Top	Bot	Thru	Comments
4893	4899		
3446	3450		
3118	3124		
3026	3034		
3005	3012		
2931	2938		
2740	2744		
2718	2722		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: TBG

RECEIVED
JAN 25 2012
KCC WICHITA

District: 01

Signed Jack MacLasky
(TECHNICIAN)

RECEIVED
JAN 23 2012
KCC DODGE CITY

Form CP22/3
1/30/12