

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-129-20217-00-00  
Spot: SWNENWNW Sec/Twnshp/Rge: 7-33S-40W  
487 feet from N Section Line, 894 feet from W Section Line  
Lease Name: SANTA FE TRAIL UNIT A Well #: 3-4  
County: MORTON Total Vertical Depth: 5450 feet

Operator License No.: 34408  
Op Name: CISCO OPERATING LLC  
Address: 6900 N. DALLAS PKWY, STE 740  
PLANO, TX 75024

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5328		WITH 5 SX CMT
SURF	8.625	1504		WITH 800 SX CMT
PROD	4.5	5445	1856	WITH 150 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 01/18/2012 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: SET CIBP @ 5328' WITH 2 SX CMT. SHOOT 4 1/2" & POOH. PLUG AT 1634' WITH 80 SX CMT. PLUG AT 700' WITH 60 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: KENNY SULLIVAN Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 01/19/2012 9:00 AM KCC Agent: JACK MACLASKEY

Actual Plugging Report:

1/18/12: SET CIBP @ 5328' WITH 5 SX CMT. CIRCULATE HOLE WITH MUD, SPOT 60 SX CMT AT 4000'. SDON. 1/19/12: SHOT 4 1/2" @ 1856' & POH. RIH W/TBG TO 1704' & PUMP 100 SX CMT. POH W/TBG & LET SET 2 HOURS. TAG TOC @ 1339'. RIH W/TBG TO 650' & PUMP 80 SX CMT. TOP WELL OFF AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5378	5394		MORROW

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

RECEIVED  
JAN 25 2012

KCC WICHITA

District: 01

Signed

Jack MacLaskey  
(TECHNICIAN)

RECEIVED

JAN 23 2012

KCC DODGE CITY

Form CP-23

1/30/12