

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-129-20319-00-00

Spot: SWSE

Sec/Twnshp/Rge: 6-33S-40W

692 feet from S Section Line, 1980 feet from E Section Line

Lease Name: SANTA FE TR

Well #: A-2-2

County: MORTON

Total Vertical Depth: 5440 feet

Operator License No.: 34408

Op Name: CISCO OPERATING LLC

Address: 6900 N. DALLAS PKWY, STE 740
PLANO, TX 75024

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		5283		WITH 5 SX CMT
SURF	8.625	1605		WITH 800 SX CMT
PROD	4.5	5440	2004	WITH 200 SX CMT

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 01/16/2012 9:00 AM

Plug Co. License No.: 33338

Plug Co. Name: ORR ENTERPRISES, INC.

Proposal Rcvd. from: RONNIE ORR

Company: ORR ENTERPRISES, INC.

Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 5300' WITH 2 SX CMT. PLUG AT 1635' WITH 80 SX CMT. PLUG AT 700' WITH 60 SX CMT. PLUG AT 40' TO SURFACE.

Plugging Proposal Received By: STEVE DURRANT

WitnessType: NONE

Date/Time Plugging Completed: 01/16/2012 5:00 PM

KCC Agent: STEVE DURRANT

Actual Plugging Report:

RIH W/SAND LINE & TAGGED TD @ 5290'. 1ST PLUG SET CIBP @ 5283' WITH 5 SX CMT. CIRCULATED HOLE WITH 70 BBL. SHOT 4 1/2" CASING @ 2004'. POOH W/CASING. 2ND PLUG RIH W/TBG TO 1637' & PUMPED 80 SX CMT. 3RD PLUG POOH TO 700' & PUMPED 60 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5337	5358		MORROW

Remarks: USED CLASS C CEMENT BY ORR ENTERPRISES.

Plugged through: CSG

RECEIVED

JAN 25 2012

KCC WICHITA

District: 01

Signed

Steve Durrant

(TECHNICIAN)

RECEIVED

JAN 23 2012

KCC DODGE CITY

FORM 2/3

✓ 1/30/12